

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

84

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 8W 81

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling
in Section

S 6 T 44N R 8W 8

S _____ T _____ R _____ _____

3. Miscellaneous

S _____ T _____ R _____ _____

Property in Sec.

S _____ T _____ R _____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 18 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(81) North Quarter corner, Section 6. Corner not established in the original survey. Corner re-witnessed and recorded in 1969 by Billy D. Buckler, RLS: This corner was re-witnessed as set by unknown surveyor. Found 2" iron pipe in 8" concrete monument. Found a 1/2" iron rod 12.2' west of this monument...appears to be the 1/4 corner of Sec. 31, to north. 5" Red Pine S14E 27.7', 14" Hard Maple clump N20E 40.6'.

(8-Sec. 6) West 1/16 corner, Section 6. Corner not established in the original survey. Recorded in 1969 by Billy D. Buckler, RLS: "Found 2" iron pipe in 8" concrete monument. Re-Witnessed monument as set by unknown surveyor. Cor. lies approx in line with road to north and east. Fence corner bears S44W 22.0'. A fence further south lines with the corner. 15" Elm S75W 33.9". Found no other record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(81) Found the 2" iron pipe in 8" concrete base as described, in good condition, and at record bearing and distance from Buckler's 1969 accessories. Left the monument in place and made new witnesses as described below. The monument was found 0.62' north of the township line defined by adjacent standard corners, and 6.07' west of the proportionate position. Accepted same as a careful and faithful determination of the position of the corner.

(8-Sec. 6) Found the monument as described above in Section A. The Elm witness is now dead and gone. Determined that the monument is 15.02" South and 21.49' east of the proper position for the corner and did not accept it as marking the position of the 1/16 corner. Established the corner at 20 chains, proportionate to the original record, west of the monumented Center of Section 6 and on a straight line between the Center and the Quarter corner common to Section 6 44N-8W and Section 1 44N-9W. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The Center of Section 6 is 1320.74' East, and the Quarter corner is 1269.23' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(81) Found 2" iron pipe in concrete.
Blazed, scribed, and set measuring nails
in the following:

14" R. Pine S14E 28.3' "1/4S"
18" H. Maple clump N20E 41.0' "1/4S"
(both above are 1969 rec. bearings)
6" R. Pine S62E 16.05' "1/4S NBT"
Found MDNR monument West 12.15' at South
1/4 S31, 45N-8W. Placed location poster
270' south at E-W trail.

(8) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

8" Squared aspen S15W 0.7' "N1/16 BT"
3" Cherry S60E 10.5'
4" Cherry N31E 17.3'
The monument described in 1969 is 953E
26.29'
Placed a location poster 4 ft. west on
N-S trail. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-29-95

For the Michigan Department of Natural Resources - Forest Management Division