

82

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac

Located in:

Corner Code #

County

1. Public Land Survey

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S 6 T 44N R 8W 6

S 6 T 44N R 8W 5

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

5 Aug 30 1995

6 Aug 29 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2	5			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 (6-Sec. 6) Northeast 1/16 corner, Section 6. Corner not established in the original survey. Found no subsequent record.  
 (5-Sec. 6) North 1/16 corner Section 6. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corner to the north is not monumented. At the position for the corner I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found an axle shaft placed by unknown persons 42' north and 61' east.  
 (5-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner 20 chains, proportionate to the original record, north of the Center of Section 6 and on a straight line between the center and the North 1/4 corner of Section 6, both found monumented. The Center is 1326.60' south and the 1/4 corner 1296.59' north. At the position for the corner I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1" iron pipe placed by unknown persons, projecting about 2 ft., 61.6' north and 13.3' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (6) Set 1" pipe with 4" MDNR cap.   | (5) Set 1" pipe with 4" MDNR cap.                                |
| Blazed, scribed, and set measuring nails in the following trees:              | Blazed, scribed, and set measuring nails in the following trees: |
| 5" W. Birch S10E 44.2' "NE1/16 BT"  | 10" R. Pine N02E 11.4' "N1/16 BT"                                |
| 14" R. Pine N34W 65.9'  | 14" R. Pine N32E 42.65'  |
| 12" R. Pine N30W 85.3'  | 12" R. Pine N27W 7.15'   |
| Found Axle shaft N60E 74.02'  | 12" R. Pine S78W 27.6'   |
| Placed a 4" Cedar post, squared and scribed, adjacent. Bearings are magnetic. | Found 1" pipe N09W 63.01'  |
|   | Edge of plantation 54' West. Bearings are magnetic.              |



Signed by Stephan J. Szyszkoski Date 11-29-95

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division