

81

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 8W 82

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 18 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		●		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(82) Center of Section 6. Corner established in 1974 by Billy D. Buckler, RLS at the intersection of 1/4 lines. Buckler placed a 1' pipe and 1/2" re-rod at corner, in North half of road. USGS MON. N60E 47.1', NE cor. Building, S29W 72.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(82) Recovered Buckler's monument, as described, in good condition. Did not recover either 1974 witness. The building has burned down. Only the witness sign post for the USGS mon. was recovered. Determined that the monument is 2.19' south of a straight line connecting the East and West 1/4 corners of Section 6. I accepted the monument as a careful and faithful determination of the position of the corner. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(82) Found 1' pipe with 1/2" re-rod in

E-W road. Blazed, scribed, and set

measuring nails in the following:

6" R. Pine N60W 82.4' CS 81"

6" R. Pine N48W 94.9' "

6" R. Pine North 58.4' "

Found a USGS witness post N60E 47.4'

Placed a location poster 15' north.

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

11-29-95

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division