

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MacKinnac Located in: \_\_\_\_\_ Corner Code KS  
(County)

1. Public Land Survey T 44N R 8W \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on October 13, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	14	15	16	17	18						
7												
8	19	20	21	22	23	24						
9												
10	25	26	27	28	29	30						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(KS) Corner common to Sections 11-12-13-14. Corner re-monumented by Billy D. Buckler, RLS in 1968 as follows: "This corner replaced at wood post placed by Marcus Schaaf, R.L.S. about 1934. Found remains of W. Pine stump for original witness. Corner lies about 20' north of an old logging trail and 8.00 chains south of the Giddings truck trail". Buckler placed a 1" pipe with 4" aluminum cap at the corner and marked the following NBTs: 34" W. Pine stump N77W 28.8', 8" B. Cherry S31E 25.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(KS) Found Buckler's 1968 monument, as described, in good condition, at record bearing and distance from his 1969 NBTs. The B. Cherry is now dead but the scarred-over blaze is visible. Left the monument in place and marked 4 new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(KS) Found 1" iron pipe with 4" aluminum MONR tablet. Blazed and set measuring nails with tags in the following new bearing trees:  
6" Spruce N05E 9.45'  
3" W. Birch N05E 24.50'  
8" Aspen S25E 20.95'  
3" Balsam N74W 18.60'  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-9-95  
Surveyor's Michigan License No. 33986