

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macinaac
(County)

Located In:

Corner Code **≠**

1. Public Land Survey	T	<u>44N</u>	R	<u>8W</u>	<u>I13</u>		
	T	<u>44N</u>	R	<u>8W</u>	<u>K13</u>		
	T		R				
	T		R				
2. Property Controlling In Section	S	<u>35</u>	T	<u>44N</u>	R	<u>8W</u>	<u>11</u>
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Stephan J. Szyszkoski, in a field survey on March 04, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (I13) Section corner common to Sections 34-35, T44N-R8W and Sections 2-3, T43N-R8W. Corner previously recorded in 1969 by Billy D. Buckler, RLS as monumented by a 5/8" iron pin driven in center of E-W road and the following witnesses: 15" W. Birch (NBT) S18E 45.4', 10" N. Maple (NBT) N23W 65.4'. Found no subsequent record.
 (K13) Section corner common to Sections 35-36, T44N-R8W, and Sections 1-2 T43N-R8W. Corner previously recorded in 1968 by Billy D. Buckler, RLS as monumented by a 5/8" iron bar, buried in road intersection, and the following witnesses: 16" W. Spruce (S35 NBT) 37W 62.0', U.S. Geological Survey Monument T782S N25E 70.6'. Found no subsequent record.
 (11) Southwest 1/16 corner, Section 35. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (I13) Found and accepted a 5/8" iron pin as described above with the exception of distance to N. Maple N23W. Distance was found to be 64.5', an apparent transposition error in the 1969 record. Both 1969 NBTs were found alive. Placed measuring nails and tags in these trees, and took two new witnesses as described below.
 (K13) Found and accepted a 5/8" iron bar at record bearing and distance from the 1968 witnesses (W. Spruce was found to be N37W). Took two new witnesses, as described below.
 (11) Found no evidence of prior monumentation at corner location. Established corner at the intersection of straight lines connecting opposite 1/16 corners, the 1/16 corners to the west and south being unmonumented. From the corner established, an old N-S fence is approximately 60' west, and a post row of metal fence posts which is an extension of an old fence located south of the railroad is about 5' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|--|
| (I13) Found 5/8" iron pin in center of E-W road.
Placed measuring nails and tags in the 1969 NBTs as follows:
20" W. Birch S18E 45.65'
14" N. Maple N23W 64.95'
New witnesses:
12" N. Maple N44E 70.6' nail/MOHR tag
Iron fence post N04E 33.15' | (K13) Found 5/8" iron bar.
Set measuring nail and MOHR tag in the 1968 NBT:
26" W. Spruce N37W 62.2'
Set nails with MOHR tags in the following new witnesses:
8" Cedar N48E 51.35'
P. Pole E-31 S45E 63.35' | (11) Set a 1"x32" iron pipe capped with a 4" dia. cast aluminum MOHR tablet.
Blazed, scribed, and set measuring nails in the following bearing trees:
16" Maple S72E 12.9' (1/16S BT)
3" Maple N62E 19.95' (1/16S BT)
20" Maple N27E 29.8' (1/16S BT)
10" Maple N45W 24.1' (1/16S BT)
Placed a squared wood post adjacent to the monument. |
|--|--|--|

Signed by Stephan J. Szyszkoski Date 4-5-93
 Surveyor's Michigan License No. 33986

