

77

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>35</u>	T	<u>44N</u>	R	<u>8W</u>	<u>12</u>
	S	<u>35</u>	T	<u>44N</u>	R	<u>8W</u>	<u>13</u>
3. Miscellaneous Property in Sec.	S	<u>35</u>	T	<u>44N</u>	R	<u>8W</u>	<u>8</u>
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkowski, in a field survey on March 04, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	13	14	15	16	17	18	19	20	21	22	23	24	25
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	25	26	27	28	29	30	31	32	33	34	35	36	37
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (12) South 1/16 corner, Section 35, T44N-R8W. Corner not established in original survey. Found no subsequent record.
(13) Southeast 1/16 corner, Section 35. Corner not established in the original survey. Found no subsequent record.
(8) West 1/16 corner, Section 35, T44N-R8W. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12) Established corner midway and on a straight line between the recorded Quarter corner common to Sections 35 & 2, and the unmonumented Center of Section 35, the center being the intersection of straight lines connecting opposite 1/4 corners, all monumented.
(13) Found no evidence of prior monumentation at corner location. Established the corner at the intersection of straight lines connecting opposite 1/16 corners, the 1/16 corners to the north and east being unmonumented.
(8) Found no evidence of prior monumentation at corner location. Established the corner midway and on a straight line between the monumented Quarter corner common to Sections 34 & 35, and the unmonumented Center of Section 35, the Center being the computed intersection of straight lines connecting opposite Quarter corners, all monumented. From the corner established, an old fence intersection with fencelines extending west and south was found approximately 47' west and 37' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| (12) Set a 1"x32" iron pipe capped with a 4" cast aluminum MDNR tablet. Blazed, scribed, and set measuring nails in the following bearing trees:
6" Maple clump S57E 34.1' (1/16S BT)
Twin 6" Maples N44E 26.15' (1/16S BT)
Twin 8" Maples N12E 39.05' (1/16S BT)
30" Maple S38W 37.6' (1/16S BT)
Placed squared post adjacent to monument. Corner lies about 100' north of railroad. | (13) Set a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed, scribed, and set measuring nails in the following bearing trees:
6" Jack Pine S40E 27.9' (1/16S BT)
8" Spruce S66E 29.9' (1/16S BT)
10" Maple N58E 40.3' (1/16S BT)
6" Ironwood N06E 25.95' (1/16S BT)
Placed a squared wood post adjacent to the monument. Corner lies about 60' north of the railroad. | (8) Set a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed, scribed, and placed measuring nails in the following bearing trees:
12" Maple N63E 12.95' (1/16S BT)
5" Maple N12E 19.6' (1/16S BT)
5" Maple N74W 27.75' (1/16S BT)
4" Jack Pine S70E 52.55' (1/16S BT)
Placed squared post alongside monument. |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Signed by Stephan J. Szyszkowski Date 4-5-93

Surveyor's Michigan License No. 33986

