

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MacKINAC
(County)

Located In: _____ Corner Code: 112

1. Public Land Survey	T <u>44N</u> R <u>8W</u>	<u>112</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on March 04, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(112) 1969: Corner recorded by Billy D. Buckler RLS, as reestablished midway and on a straight line between section corners north and south. 1" pipe with 4" aluminum cap was placed for the corner and the following NBT's were marked: 14" Elm (1/4S NBT) S15E 62.4', 17" Elm (1/4S NBT) N68W 34.4'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(112) Found and accepted record 1" pipe with 4" aluminum cap. 1969 bearing trees are both dead. Marked 4 new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

(112) 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following new bearing trees:
4" Maple S27E 21.2' arkd "1/4S NBT"
4" Maple S40W 42.25' arkd "1/4S NBT"
3" Cherry N84W 35.75' arkd "1/4S NBT"
3" Maple N54E 42.15' arkd "1/4S NBT"
placed iron fence post on east side of monument.



Signed by Stephan J. Szyszkoski Date 4-5-93
Surveyor's Michigan License No. 33986