

MACKINAC COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
 (County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>8W</u> | <u>E-5</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED & FILED
DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995
 AM 7 | 8 | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | 6 PM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James H. Granger, in a field survey on October 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 Original Survey set wood post 8" tamarack S39°E 5 lks. 8" tamarack N13°W 6 lks.
 H. Brevoort

1960 DNR-Billy Buckler set 1/2" iron
 #8887

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" iron in CL road opposite wood post with DNR identification tag. DNR witnesses gone.

SURVEY &
 REMONUMENTATION

DEC 01 1995

COMMISSION


ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELD ON 9-18-95

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rebar with Remonumentation Cap.

- | | | | |
|-----------|--------|--------|---------|
| 8" cedar | N 66°E | 35.94' | set tag |
| 6" spruce | S 35°E | 45.46' | set tag |
| 8" cedar | S 41°W | 63.08' | set tag |
| 12" cedar | N 47°W | 47.58' | set tag |



Signed by James H. Granger

Date 10/27/95

Surveyor's Michigan License No. 16041