

**SURVEY &
REMONUMENTATION**

OCT 11 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION

Mackinac

(County)

Located In:

Corner Code #/

- | | | | | | | |
|---------------------------------------|---|------------|---|-----------|-------------|-------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>8W</u> | <u>E-10</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED & FILED
MACKINAC COUNTY BOARD OF LAND SURVEYORS

SEP 6 1994

AM 7:10 PM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James H. Granger, in a field survey on August 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 Original Survey set wood post
H. Brevoort 4" Beech N16°W 23 lks.
6" Beech S52°W 38 lks.

1961 DNR set 3/8" bar
Billy Buckler #8887

1979 DNR set "T" iron
Billy Buckler #8887

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


found "T" iron and 4 witnesses

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 8-16-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

set 5/8" rerod w/alum. cap
14" maple N60°W 96.50' tag #31591
5" spruce west 42.55' tag #31591
7" aspen S70°E 59.89' tag #31591
6" birch east 76.98' tag #31591



Signed by James H. Granger Date August 30, 1994
Surveyor's Michigan License No. 16041

09-06-94

HEBER

D-0235