

SURVEY & REMONUMENTATION

MACKINAC COUNTY REMONUMENTATION CORNER

OCT 11 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
Mackinac
(County)

Located In: Corner Code E-11

- | | | | | | |
|------------------------------------|---|------------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>8W</u> | <u>E-11</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

RECEIVED & FILED
 DEANE BOADTOWNICH
 MACKINAC COUNTY REGISTER OF DEEDS

SEP 6 1994
 AM PM
 7181910111213141516

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James H. Granger, in a field survey on August 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 original survey set wood post
 H. Brevoort 12" beech N 6°E 40 lks.
 12" beech N40°W 26 lks.

1960 DNR set 1/2" bar
 Billy Buckler #8887

1975 survey fd 1/2" bar; set 1" pipe over bar
 Lawrence Feindt #21566

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

fd 1" pipe over 1/2" bar and 4 witnesses

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

set 5/8" rerod w/alum. cap

- 8" cherry S76°W 38.90' tag #31591
- 8" cherry N63°W 35.65' tag #31591
- 13" pine N78°E 39.50' tag #3920
- 8" pine S72°E 39.84' tag #22435



Signed by James H. Granger Date August 30, 1994
 Surveyor's Michigan License No. 16041