

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac
 (County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>8W</u> | <u>E1</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Aug 12 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E1) Closing corner between Sections 4-5. Reestablished in 1960 by Billy D. Buckler RLS. 1" pipe with 4" brass cap. 9" W. Spruce S76E 78.5 links. Standard corner for Sections 32-33, T45N-R08W is 27 links west.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E1) Recovered the 1960 Spruce NBT and a MI Dept. of Conservation monument at the standard corner. The 1960 monument was not recovered. Re-monumented the corner at record bearing and distance from the Spruce and at 17.82' east of the standard corner. At the position for the corner I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E1) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:
 14" Spruce S74E 52.3' "S4"
 5" Maple S68E 12.15' "S4 NBT"
 5" Maple S14E 23.3' "S4 NBT"
 Bearings are magnetic. Distances are to nail w/tag. 1" pipe with 4" brass cap recorded as E13, T45N-R08W, is 17.82' west.



Signed by Stephan J. Szyszkoski Date 4/18/00
 Surveyor's Michigan License No. 33986