

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In: Corner Code #

- 1. Public Land Survey T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S 36 T 44N R 8W 13
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

May 21 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:


(13-Sec. 36) Southeast 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The corner monument falls in with the easterly extension of a fence, course west. A N-S fence is 10' west of the corner.

C. Description of monument for corner and accessories established to evaluate locating the position of the corner:

(13) Set 1" IDx36" iron pipe with 4" alum. MDNR cap. Blazed, scribed and set measuring nails in the following trees:
14" Maple N73W 24.6' "SE1/16 BT"
16" Maple clump N65W 19.7' do
fence post S27E 89.9' nail and tag
fence post S18W 72.0' nail and tag
Placed wood post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by

Stephan J. Szyszkoski

Date

1/16/02

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management