

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S <u>32</u>	T <u>44N</u> R <u>8W</u>	<u>4</u>
	S <u>32</u>	T <u>44N</u> R <u>8W</u>	<u>3</u>
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 19 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (4-Sec. 32) Northwest 1/16 corner, Section 32. Not established in the original survey.
 (3-Sec. 32) North 1/16 corner between Sections 31-32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (4-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (3-Sec. 32) Established the corner midway and on line between Section Corner 1336.68' north and Quarter corner 1336.68' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in: 10" Cedar S04E 32.15' mrkd "N1/16 BT" 12" Cedar S38W 7.1' do 10" W.Birch N76W 14.7' do 12" Cedar N32W 20.75' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in: 14" Cedar N20E 8.15' mrkd "N1/16 BT" 6" Cedar S47E 3.85' do 4" Cedar S25W 2.1' do 10" Cedar N87W 7.95' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski Date 10/21/04
 Surveyor's Michigan License No. 33986