

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

| | | |
|---------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>44N</u> R <u>8W</u> | <u>C12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u>32</u> T <u>44N</u> R <u>8W</u> | <u>14</u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

14 Sep 28 2004

C12 Oct 19 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(C12) Quarter corner common to Sections 31-32. 1845 - Established by H. Brevoort, Deputy Surveyor: North between Sec. 31&32 ... 40.00 Set qr. sect. post. Birch 6 N38W 21 links, Birch 6 S69W 24 links ..80.00 Set post Cor. Sec. 29-30-31-32.
 (14-Sec. 32) South 1/16 corner between Sections 32-33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C12) The original post and accessories were not recovered. Reestablished the corner midway and on line between Section corners 2673.36' north and south. From the corner thus established, found a squared post with tag stating "approx. cor" by Champion International in downed E-W barbed wire fence N28E approx. 50' distant.
 (14-Sec. 32) Established the corner midway and on line between Quarter corner 1320.17' north and Section corner 1320.17' south. The corner falls in a N-S asphalt-paved road, approx. 1.5' west of the C/L as constructed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| (C12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in: 8" Maple N46E 10.05' mrkd "1/4S N8T" 14" Maple S58E 15.35' do 10" Maple S14E 28.1' do 10" twin Maple N75W 42.05' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (14) Set 5/8"x36" rerod with plastic cap "MICH DNR PS33986". Set measuring nails with tags in: 10" J.Pine S68W 87.85' mrkd "S1/16 BT" 20" twin Maple N42W 64.25' do 10" R.Pine N60E 45.75' do 8" J.Pine S67E 45.8' do Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/27/04