

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>8W</u>	<u>M11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Jul 20 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M11) Standard Section corner common to Sections 25 and 36 T44N-R08W. Remonumented in 1958 by Billy D. Buckler RLS in the original position as perpetuated by Marcus Schaaf, RLS. Mr. Buckler's record is dated 6/18/59. Set 1" pipe with 4" brass cap. Witnesses to corner: 13" Yellow Birch N36W 7 links, 5" Cedar S5W 34 links. Mr. Buckler states that the Closing corner for Sections 30-31 T44N-R07W lies 18 links north of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M11) Recovered the 1958 monument in good condition and at record bearing and distance from the 1958 witnesses trees, both in good condition. The monumented closing corner to Sections 30-31 T44N-R07W was found 12.24' north. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and made new marks on the 1958 NBTs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M11) Found 1" ID I. pipe with 4" brass Mich. Dept. of Conservation cap. Set measuring nails in:
 6" Cedar S36E 5.8' mrkd "S31 NBT"
 5" Cedar N64W 19.95' "S25 NBT"
 20" Y. Birch N31W 4.8' mrkd "S25" *
 10" Cedar S03W 22.6' "S35" *
 Bearings are magnetic. Distances are to nail with tag. * denotes 1958 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1/26/06