

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY  
T 44N R 9W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 10-11-14-15

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-27-68

WITNESSES TO CORNER..... 10" R. Pine (S11 NBT) N17°E 100.2'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on line bet. corners to north and south.  
Found no evidence of original or of post set by Marcus Schaaf, R.L.S. in 1934.  
At that time Schaaf set this corner by record distance to several swamp edges  
and a line tree to west.

Cor. lies 48.0' east of fence line.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler, R.L.S.  
REGISTERED LAND SURVEYOR

DATE

3-17-69

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68