

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY
T 44N R 9W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 14-15-22-23

CORNER MONUMENT 1" pipe with 4" aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 8-6-68

WITNESSES TO CORNER..... 7" W. Pine (S22 NBT) S67°W 12.0'



7" W. Pine (S14 NBT) N23°E 17.9'

AND _____

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original W. Pine bearing tree; a stump bearing N2°W 29 links. Stump cut 2' high. Chopped out calloused scar and found lower blaze with scribe marks "BT" and overgrowth in good condition.

Corner lies 2.0' west of fence line; found iron fence post, N19°E 8.3'
Corner lies 95' north of old road.

Corner lies 64.5' north and 4.8' west of 528.0' fr. North.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE

3-14-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing