

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 44N N.R. 8-9W

Mackinac COUNTY


DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 19-24.

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-6-70

WITNESSES TO CORNER..... 9" W. Birch (1/4 S MBT) S48°W 8.3'

9" Cedar (1/4 S MBT) S53°E 48.6'



AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line bet.
Two Sec. Cor.
Found no evidence of original corner or witnesses.

Corner lies on South end of a sand ridge and in an old camp site. There is a
clearing from the corner, 200' North.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 8-26-70
REGISTERED LAND SURVEYOR