

7

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Hackinac

(County)	Located in:	Corner Code #
1. Public Land Survey	T 44N R 9W	M2
	T 44N R 9W	M1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 18 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(M2) Quarter corner common to Section 1 T44N-R9W and Section 6 T44N-R9W. Corner recorded in 1969 by Billy D. Buckler, RLS: Found 2" iron pipe set on an old fence line. 11" Hard Maple S60W 39.0', 12" Hard Maple clump N31E 58.5'
(M1) Corner common to Townships 44N-45N, Ranges 8W-9W. Corner re-witnessed and recorded in 1969 by Billy D. Buckler, RLS: 2" iron pipe in 8" concrete monument. Found two 2" iron pipes, placed as witnesses, bearing N45W 45.0' and S45E 45.0'. Fence corner 33.0' West of corner. 8" Hard Maple N01N 18.8', 8" Hard Maple S60W 20.0'. Monument lies in line with roads to north and east.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M2) Found the 2" iron pipe as described, in good condition, and at record bearing and distance from the 1969 witnesses. Left the pipe in place and marked two new witnesses.
(M1) Recovered the 2" pipe monument as described, in good condition, and at record bearing and distance from the 1969 witness H. Maple S60W. The other witness had been cut. Left the pipe in place and marked three new witness trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M2) Found 2" iron pipe. Blazed, scribed, and set measuring nails in the following: 14" H. Maple S60W 39.6' "1/4S" 12" H. Maple N31E 57.95' "1/4S" (both above bearings are 1969 record) 6" Cherry S26W 13.35' "1/4S NBT" 6" Elm N80W 19.1' "1/4S NBT" (Bearings magnetic) Placed a location poster 155' north on an E-W trail.	(M1) Found 2" pipe in 8" concrete base. Blazed, scribed, and set measuring nails in the following: 10" H. Maple S60W 20.3' "S1" (Above is 1969 rec. bearing) 3" Aspen N55W 5.2' "S36 NBT" 4" Aspen N35E 4.5' "S31 NBT" 5" H. Maple S25W 16.9' "S1 NBT" Bearings magnetic. Placed a location poster 85' east at a N-S trail.
---	--



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-29-95

For the Michigan Department of Natural Resources - Forest Management Division