

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#26

For corners in
Mackinac

Located In: Corner Code #

(County)

- | | | |
|---------------------------------------|--|-----|
| 1. Public Land Survey | T ^{44N} R ^{9W} | J13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S ³⁵ T ^{44N} R ^{9W} | 15 |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jan 25 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (J13) Quarter corner common to Section 35 T44N-R9W and Sec. 2 T43N-R9W. Corner re-monumented in 1969 by Billy D. Buckler, RLS as follows: This corner replaced at an old squared wood post, set by unknown surveyor. Position checks well with corner 1/2 mile west. Found remains of hemlock stump in vicinity but could identify none as the original witnesses. Corner lies in wet swamp. Corner monument 1" pipe with 4" aluminum cap. Witnesses: 9" W. Pine S80W 34.7', 9" Tamarack S34E 8.0'.
- (15-Sec. 35) West 1/16 corner on south line of Section 35. Corner established in 1968 by Billy D. Buckler, RLS, midway and on line between Sec. Cor. to west and 1/4 cor. to east. Corner was monumented with a 1" pipe with 4" aluminum cap and the following witnesses: 10" W. Pine S53E 13.7', 6" Soft Maple N55E 24.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J13) Found the monument as described above, in good condition, and at record bearing and distance from the 1969 witnesses, both in good condition. Left the monument in place, placed measuring nails in the 1969 accessories, and marked two new trees as described below.
- (15-Sec. 35) Found Buckler's monument as described, in good condition, and at record bearing and distance from his 1968 accessories, both in good condition. Re-blazed both at BH. Left the monument in place and marked three new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (J13) Found 1" pipe with 4" Al Dept. of Conservation cap. Blazed, scribed, and set measuring nails in: | (15) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: |
| 10" W. Pine S80W 34.9' "1/4S" | 14" W. Pine S53E 14.05' "W1/16" |
| 12" Tamarack S34W 7.5' "1/4S" | 8" Soft Maple N55E 24.6' "W1/16" |
| 10" W. Pine S03W 27.9' "1/4S N8T" | 6" Soft Maple N45E 22.65' "W1/16 BT" |
| 5" Cedar N61E 11.1' "1/4S N8T" | 5" Soft Maple N22E 17.6' "W1/16 BT" |
| Bearings are magnetic. | 5" Spruce S06W 6.95' "W1/16 BT" |
| | Placed location poster West 196' at W. side of trail. Bearings are magnetic. |

