

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T44N R 9W M11  
T44N R 9W K11

2. Property Controlling  
in Section

S T R  
S T R

3. Miscellaneous  
Property in Sec.

S T R  
S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

K11 Jan 08 2007  
M11 Dec 20 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(M11) Corner common to Sections 25-36 T44N-R09W and 30-31 T44N-R08W. 1958 - Perpetuated by Billy D. Buckler RLS at a position monumented by Marcus Schaaf RLS, and at record bearing and distance from an original Tamarack BT. Set 1" pipe with 4" brass cap. 5" B.Spruce N89E 61.5 links, 4" B.Spruce N78W 70 links.

(K11) Corner common to Sections 25-26-35-36. 1968 - Billy D. Buckler RLS monumented the corner from "one probable B.T.; a W.Pine stump bearing N44E 14 links". Set 1" pipe with 4" aluminum cap. 18" R.Pine East 35.8', 6" R.Pine S41W 41.2'. I note that the GLO record states that the W.Pine BT bears N44E 18 links from the corner. Since I have in front of me the very copy of the GLO record that Mr. Buckler examined, I presume that his 1969 record contains a typographical error.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M11) Recovered the 1958 monument in good condition and at record bearing and distance from the remaining B.Spruce NBT N78W (N72W meas.), now 6" DBH. The other 1958 NBT was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(K11) Recovered the 1968 monument in good condition and at record bearing and distance from the 1968 witness trees, both still in good condition. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M11) Found 1"ID I.pipe with 4" brass cap. Set measuring nails in:  
6" B.Spruce N72W 46.3' with old marks \*  
6" B.Spruce N47W 60.35' mrkd "S25 NBT"  
8" B.Spruce N13W 75.4' do  
7" B.Spruce S73E 57.35' "S31 NBT"  
Bearings are magnetic. Distances are to nail with tag. \* denotes 1958 NBT

(K11) Found 1"ID I.pipe with 4" alum. cap. Set measuring nails in:  
20" R.Pine S87E 36.4' mrkd "S25" \*  
8" R.Pine S43W 41.35' old marks \*  
7" W.Pine N45E 13.65' mrkd "S25 NBT"  
7" W.Pine S22W 49.9' "S35 NBT"  
Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 5/16/07

For the Michigan Department of Natural Resources