

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N., R. <u>10</u> X W.	G-3, G-2, E-3
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8/12 & 6/3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
All corners set by Wm. Ives, D.S. in 1849.

<p>G-3 Sec. Cor. 3-4-9-10. Bearings were: Tam. 8, S52°W, 57 lks. Tam. 7, N45°E, 36 lks.</p>	<p>G-2 $\frac{1}{4}$ Cor. Bet. Sec's. 3-4. Bearings were: Tam 5, S63°E, 38 lks. Tam 6, N57°W, 44 lks.</p>	<p>E-3 Sec. Cor. 4-5-8-9. Bearings were: Hemlock 8, N72°W, 08 lks. W. Birch 18, S50°E, 46 lks.</p>
---	--	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-3 Placed corner by single prop. measure to North and South and in road. Found no evidence of original corner.

G-2 Corner re-established by single prop. measure bet. two Sec. Cors. Corner lies in East part of County Road.


E-3 Placed section corner record distance (307.56') East of an original W. Pine line tree. Found a re-rod at Dept. of Hwy. location, which is 9.0' North and 25.92' West of our corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 and G-2 buried 36" "T" iron at corners. E-3 placed 1" pipe with 4" aluminium cap.

<p>G-3 New Bearing: 6" Tamarack, S85°E, 24.3'</p>	<p>G-2 New Bearings: 6" Tam, N60°E, 54.8' 6" Tam, S28°E, 81.7'</p>	<p>E-3 New Bearings: 12" Spruce, S27°E, 47.7' Corner lies 59.06' East of center line M-117.</p>
---	--	---

SIGNED BY Billy D. Buckler DATE 9/20/77
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____