

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____ N. _____ S., R. _____ E. _____ W.		4A-Sec.9
2. PROPERTY CONTROLLING IN SECTION <u>9</u> , T. <u>44</u> N. _____ S., R. <u>10</u> E. _____ W.		1A-Sec.9 7-Sec.9
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8/12, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 4A-Sec.9 Corner is midway on South side of NE $\frac{1}{4}$ of NW $\frac{1}{4}$.
- 1A-Sec.9 Corner is midway on North side of NE $\frac{1}{4}$ of NW $\frac{1}{4}$.
- 7-Sec.9 North 1/16 corner on Eastside of Section 9.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 4A-Sec.9 Corner placed midway on south side of NE $\frac{1}{4}$ of NW $\frac{1}{4}$, dividing the NE $\frac{1}{4}$ of NW $\frac{1}{4}$ into the East half and the West half.
- 1A-Sec.9 Corner placed midway on North side of NE $\frac{1}{4}$ of NW $\frac{1}{4}$.
- 7-Sec.9 Corner placed midway bet. section corner North and $\frac{1}{4}$ corner to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4A-Sec.9 Placed 1" pipe with 4" aluminium cap at corner. New Bearings: 10" Cherry, N18°W, 9.2' and 8" Cherry, N71°W, 6.7'.
- 1A-Sec.9 Placed 1" pipe with 4" aluminium cap at corner. New Bearings: 10" spruce, N10°W, 24.3' and 10" W. Birch, South, 26.2'.
- 7-Sec.9 Buried 36" "T" iron in East side of county road. New Bearings: 8" Cedar, S59°E, 39.2' and 6" Cedar, N61°E, 44.1'.

SIGNED BY Billy D. Buckler DATE 9/20/77
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____