

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44-45 N.R. 10 W


Mackinac and Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5, 6, 31, 32

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 11/3/60 with J. Halbach, D.F.

WITNESSES TO CORNER.....13" Hard Maple (S 31 NBT) N 33° W 61½ Links



9" Hard Maple (S 6 NBT) S 20° W 12 Links

10" Hard Maple (S 5 NBT) S 30° E 35½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measure along township line.

No evidence of original corner. Corner lies 25 links south of road.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE

2/23/61