

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 44N N. R. 10W


Mackinac COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 10-15

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-12-70

WITNESSES TO CORNER..... 8" Cedar (¼S NBT) N63°W 26.0'



6" Cedar (¼S NBT) N45°E 26.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line bet. two Sec. Cors. Found no evidence of original Cor. Distance checks well to streams both east and west of ¼ Cor.

Corner lies in a thick cedar swamp.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 12-2-70
REGISTERED LAND SURVEYOR