

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44N N.R. 10W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 10-11-14-15

CORNER MONUMENT Cedar post

DATE MONUMENT PLACED AND WITNESSED 12-8-69

WITNESSES TO CORNER..... 8" Cedar (S14 NBT) S24°E 6.0'



10" Cedar (S10 NBT) West 25.3'

10" Cedar (S11 NBT) N69°E 30.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a Tamarack stump, 4' high, bearing S33°W, 42 links. Found both upper and lower face in excellent condition. Scribe marks plain under the calloused overgrowth.

Corner lies 25.0' east of the Hiawatha Club fence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 12-3-70  
REGISTERED LAND SURVEYOR