

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Mackinac Co.

5 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	4-Sec.4, 5-Sec.4, 8-Sec.4
2. PROPERTY CONTROLL- ING IN SECTION _____	T. <u>44</u> N. S., R. <u>10</u> E. W.	11-Sec.4, 10-Sec.4
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-16, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 4-Sec.4 Northwest 1/16 Corner of Section 4.
- 5-Sec.4 North 1/16 Corner of Section 4.
- 8-Sec.4 West 1/16 Corner of Section 4.
- 11-Sec.4 Southwest 1/16 Corner of Section 4.
- 10-Sec.4 South 1/16 Corner on West side of Section 4.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**


- 4-Sec.4 Placed corner at intersection of lines quartering the NW Quarter Section.
- 5-Sec.4 Placed corner midway bet. N $\frac{1}{2}$  cor. and center corner.
- 8-Sec.4 Placed corner midway bet. West  $\frac{1}{2}$  corner and center corner.
- 11-Sec.4 Placed corner at intersection of lines quartering the South-West  $\frac{1}{2}$  Section.
- 10-Sec.4 Placed corner midway bet.  $\frac{1}{2}$  corner to North and section corner to South.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at all corners. Bearings are:

- 4-Sec.4 8" Cedar, S30°E, 39.3' & 8" W. Pine, S54°W, 34.8'. Corner lies on south side of ridge - E-W.
- 5-Sec.4 7" Cedar, S67°E, 9.9' & 8" Cedar, S6°E, 28.3' & 5" Cedar, N7°E, 30.8'.
- 8-Sec.4 6" W. Birch, N45°W, 10.8' & 6" W. Birch, S88°E, 5.3' & 7" S. Maple, N8°W, 29.7'.
- 11-Sec.4 No Witnesses Available. Corner lies in an old Beaver Pond.
- 10-Sec.4 Twin R. Maple, S46°E, 10.9' & 14" Hemlock, N60°E, 12.2' & 12" Hemlock, N7°W, 11.5'

SIGNED BY Billy D. Buckler DATE 10-8-79  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_