

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. 4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> , R. <u>10</u> E. <u>W</u>	<u>F-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>44</u> N. <u>X</u> , R. <u>10</u> E. <u>W</u>	<u>5, 11, 8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-13, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-4 Center Corner of Section 9. Not prev. set.
- 5 North 1/16 Corner of Section 9. Not prev. set.
- 11 S.W. 1/16 Corner of Section 9. Not prev. set.
- 8 West 1/16 Corner of Section 9. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-4 Placed corner at lines connecting opposite quarter corners.
- 5 Corner placed midway between center corner and N. 1/4 corner.
- 11 Corner placed at intersection of lines quartering the S.W. 1/4 section.
- 8 Placed midway between 1/4 corner and center corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D.N.R. Monuments placed at all corners. Bearings:

- F-4 5" Cedar, S89°E, 19.8' & 6" Cedar, S02°W, 5.1' & 7" Cedar, N05°W, 4.3'.
- 5 6" R. Maple, S74°E, 13.8' & 7" Spruce, N24°W, 14.8' & 12" R. Maple, N38°E, 20.9'.
- 11 10" S. Maple, N70°W, 40.1' & 10" S. Maple, N66°E, 21.7' & 9" S. Maple, S48°E, 15.9'.
- 8 7" Spruce, S44°W, 31.4' & 5" S. Maple, S52°E, 15.0' & 16" S. Maple, N34°W, 52.9'.

SIGNED BY _____

Billy D. Buckler
Billy D. Buckler

DATE 9-25-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

