

6

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 45N R 10W

11

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Feb 08 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(Ii.) Corner common to Sections 34-35 T45N-R10W and Sections 2-3 T44N-R10W. Corner reestablished in 1969 by Billy D. Buckler, RLS as follows: "This corner reestablished midway and on line bet. two Sec. Cors., one mile east and west; along township line. Found no evidence of original corner. Corner monument 1" pipe with 4" aluminum cap. Witnesses to corner: 10" Hard Maple S24W 9.2', 15" Hard Maple N30W 12.8'".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(Ii.) Found Buckler's monument as described, in good condition, and at record bearing and distance from the 1969 witnesses, both in good condition. Left the monument in place, set measuring nails in the 1969 accessories, and marked two new trees as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(Ii.) Found 1" pipe with 4" MI Dept. of Conservation cap. Blazed, scribed, and

set measuring nails in:

12" Sugar S19W 9.8' "S3"
18" Sugar N25W 13.2' "S34"
8" Beech N32E 18.2' "S35"
24" Sugar S84E 17.8' "S2"

Placed a squared cedar post adjacent.

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

7/30/96

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division