

32

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 10W	D5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S 8 T 44N R 10W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

11 Jul 17 1997
D5 Jul 23 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		●										
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(D5) Quarter corner common to Sections 8-17. Corner established in 1849 by William Ives: "...40.08 Set qr section post. Fir 6 S17E 12, Fir 7 N12W 23". Local land owner Mr. Elmer Brown told me that, prior to 1969, T.L. Jackson monumented this corner during a survey for Mr. Brown. He said that T.L. Jackson placed an "iron peg" which Mr. Brown subsequently replaced with an iron pipe.
(11-Sec. 8) Southwest 1/16 corner, Section 8. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D5) Original post and accessories were not recovered. Recovered a 1" iron pipe located in the intersection of fence lines existing to the North, South, East and West. Mr. Elmer Brown says that this pipe is the one he placed at T.L. Jackson's location. My measurements show that the pipe is 2.4' East and 25.9' South of the position proportionate to the original record. I accept the pipe as the best available evidence of the position of the original corner. At the position of the pipe I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark, Newberry District Office.
(11-Sec. 8) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. Only those South and East of this position are monumented. At the position for the corner I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D5) Set 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 8" Maple S68E 20.6' "1/4S NBT" 12" Maple S45W 15.6' "1/4S NBT" 6" Balsam N08W 7.5' "1/4S NBT" 8" Maple N50E 20.3' "1/4S NBT" Bearings are magnetic.	(11) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 12" Hemlock S68W 16.25' "SW1/16 BT" 4" Balsam S54W 22.65' "SW1/16 BT" 8" Spruce S18E 12.1' "SW1/16 BT" 10" Hemlock S40E 11.3' "SW1/16 BT" Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski Date 4-21-98
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division