

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

33

For corners in

Hackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 10W E4

T 44N R 10W C5

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jul 23 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(E4) Quarter corner common to Sections 8-9. Corner established in 1849 by William Ives: "...40.00 Set qr. section post. Newlock 12 N45E 21, Newlock 12 S25W 14". Corner reestablished by single proportionate measurement to the original record in 1977 by Billy D. Buckler, RLS. The 1977 Buckler position was used to subdivide Section 9 but was apparently not monumented during that survey.
(C5) Corner common to Sections 7-8-17-18. Corner was reestablished in 1976 by Billy D. Buckler, RLS: "Corner re-established by double proportionate measure from four directions. Found stream 660' North to check. No evidences of original corner. Placed 1" pipe with 4" aluminum cap at corner. New bearings 7° cherry NB6E 20.9', 10° cherry SO5E 51.0'. Corner lies 65' South of woods road".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) Original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between section corners 2637.00' North and South. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T. Stark.

(C5) Recovered the 1976 monument, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition. Both 1976 witness trees have been cut. The woods road noted above is grown over and not much use in locating the corner anymore. Left the monument in place and marked four new witnesses as described below. Corner recovered and witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Set 1" iron pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

6" Spruce N09E 2.55' 1/4S NBT
8" Maple N76E 13.15' 1/4S NBT
8" W. Birch S32E 10.3' 1/4S NBT
6" Spruce S16E 7.25' 1/4S NBT

Centerline of Hwy M-117 46' West.
Bearings are magnetic.

(C5) Found 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

8" W. Birch S56W 81.1' S18 NBT
6" W. Birch clump S66W 75.1' S18 NBT
Twin 3" W. Birch N64W 39.7' S7 NBT
5" Cherry N53E 111.0' S8 NBT

Placed a 5" cedar fence post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 4-21-98

For the Michigan Department of Natural Resources - Forest Management Division