

35

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>10W</u>	<u>C3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>8</u> T <u>44N</u> R <u>10W</u>	<u>7</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

7 Jul 23 1997
C3 Jul 22 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4		3		2		1		
3			●										
4		7		8	●	9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1976 record by Billy D. Buckler, RLS: "Corner reestablished by proportionate measure to North and South and at record distance from a fence corner 1/2 mile West. Corner lies on North edge of an old RR grade. Placed 1" pipe with 4" aluminum cap at corner. New bearings 12" B. Cherry N78E 16.6', 10" B. Cherry S40W 53.1'".

(7-Sec. 8) North 1/16 corner between Sections 8-9. 1977 record by Billy D. Buckler, RLS: "Corner set midway between Sec. Cor. to North and 1/4 Cor. to South. Placed 1" pipe with 4" aluminum cap at corner. 6" Maple N88E 6.1', 8" Maple S05W 18.7', Corner lies 52.7' East of center line M-117".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Recovered the 1976 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the SW B. Cherry witness, in good condition. Left the monument in place and marked three new accessories as described below. Corner recovered and re-witnessed by T. Stark, Newberry District Office.

(7-Sec. 8) Recovered the 1977 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the Maple NE 8T, in good condition. My measurements north to Section corner and South to reestablished Quarter corner are 1318.53' and 1318.46', respectively. This monument is 0.21' West of a straight line between them. I accepted the monument as a careful and faithful determination of the position of the corner. Left the monument in place and marked new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Found a 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

16" Cherry S38W 53.4' "S7"
5" Cherry N23E 5.5' "SS NBT"
4" Cherry N40E 5.2' "SS NBT"
6" Cherry N78E 16.1' "SS NBT"

Placed a 3" squared and scribed post adjacent. An E-W trail is 10' South. Bearings are magnetic.

(7) Found 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

8" Maple N88E 6.2' "N1/16"
14" Maple S44E 9.4' "N1/16 BT"
5" Maple S10W 13.6' "N1/16 BT"
6" Maple N04W 4.95' "N1/16 BT"
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

4-21-98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division