

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u>	Located in:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>8</u> T <u>44N</u> R <u>10W</u>	<u>15</u>
	S <u>8</u> T <u>44N</u> R <u>10W</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 17 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		●										
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (15-Sec. 8) West 1/16 corner between Section 8-17. Corner not established in the original survey. According to local land owner Elmer Brown, T.L. Jackson placed an iron pipe at or near this corner prior to 1969. 1969 field notes by Michigan Dept. of Natural Resources surveyor G.L. Wiggins show: "East between Sec. 8-17: ...1271.0 Fence line running N&S. Measured 24.0' S. to iron pipe run from M-117 by T.L. Jackson". Found no subsequent record.
 (12-Sec. 8) South 1/16 corner, Section 8. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 8) Found but did not accept as the 1/16 corner, a 1" iron pipe, apparently that placed by T.L. Jackson. This pipe does not appear to have been placed according to proper procedures as it was recovered 6.9' east and 24.6' south of the location subsequently monumented. Established the corner midway and on a line of mean true bearing between the Quarter corner 1323.43' East and Section corner 1323.43' West. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T. Stark, Newberry District Office.
 (12-Sec. 8) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1331.50' south and Center of Section 1331.50' north. The Center of Section is not monumented at this time. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1" pipe with 4" MDNR cap.	(12) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails	Blazed, scribed, and set measuring nails
in the following:	in the following:
6" Maple S06N 8.7' "W1/16 BT"	6" Cherry N26W 4.6' "S1/16 BT"
4" Balsam S87W 2.9' "W1/16 BT"	6" Maple S83E 13.4' "S1/16 BT"
5" Maple N21E 5.15' "W1/16 BT"	4" Maple S03E 7.0' "S1/16 BT"
3" Y. Birch N08W 10.4' "W1/16 BT"	6" Cherry N88W 18.75' "S1/16 BT"
Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.	Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 4-21-98
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division