

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995

AM 7 | 8 | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | 6 PM



Register of Deeds Stamp & File Number

For corners in Mackinac (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>44N</u> R <u>10W</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I David B. Guthrie in a field survey on 6/14/95, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849: Established by Wm. Ives, G.L.O. Survey - Set post and referenced Hemlock 10 - N10W - 20 / Fir 7 - S8W - 10

1994: Road Design Survey by R.S. Scott Assoc. - Set 1/2" Iron Rod at the intersection of the East West Road and a fenceline South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1/2" Iron Rod at the intersection of Sandtown Road and a fence to the South.

SURVEY & REMONUMENTATION

DEC 03 1995

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-18-95

*James H. Krueger*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 5/8"x24" Iron Rod with a 3" Aluminum Cap stamped to identify the corner. The corner was placed 6" below the gravel surface.  
Referenced - S45°W - 12" Cedar - 45.65 Feet  
S35°E - 6" Aspen - 45.04 Feet  
N30°E - 12" Spruce - 56.90 Feet  
N67°E - Utility Pole - 79.46 Feet

Signed by D.B. Guthrie Date 9/19/95

Surveyor's Michigan License No. 22435