

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

For corners in
Mackinac
(County)

Located In:

Corner Code #

NOV - 7 1995

AM PM
7|8|9|10|11|12|1|2|3|4|5|6



Register of Deeds Stamp & File Number

1. Public Land Survey T 44N R 10W C-7
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on 6/14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849: Established by Wm. Ives, G.L.O. Survey - Set post and referenced Cedar 14 - S85W - 05 / Y.Birch 12 - S79E - 20

1976: Survey by Eino Sainio - Found Iron Pipe in road.

1994: Road Design Survey by R.S. Scott Assoc. - Found 1/2" Iron Pipe at the intersection of Sandtown Road and fences North and South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1/2" Iron Pipe located at the intersection of Sandtown Road and fences North and South.

SURVEY &
REMONUMENTATION

DEC 01 1995

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-16-95

James H. Kranger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 5/8"x24" Iron Rod with a 3" Aluminum Cap stamped to identify the corner. The corner was placed 6" below the gravel surface.
Referenced - S35°W - 15" Aspen - 20.85 Feet
N41°W - 10" Scotch Pine - 51.55 Feet
North - Utility Pole - 39.60 Feet
S40°E - 14" Maple - 54.20 Feet

Signed by

D.B. Guthrie

Date

9/19/95

Surveyor's Michigan License No.

22435

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

D - 0373