

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 44N R 10W _____ D-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995
AM _____ PM _____
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on 6/14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849: Established by Wm. Ives, G.L.O. Survey- Set post and referenced Beech 9 - S34E - 35 / Y. Birch 8 - N48W - 15

1994: Road Design Survey by R.S. Scott Assoc. - Set 1/2" Iron Rod at the intersection of the East West road and a fenceline North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found 1/2" Iron Rod at the intersection of Sandtown Road and a fenceline North.

SURVEY &
REMONUMENTATION
DEC 01 1995
COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-18-95

James H. Sawyer



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 5/8"x24" Iron Rod with a 3" Aluminum Cap stamped to identify the corner. The corner was placed 6" below the gravel surface.
Referenced - North - Fence Post - 36.51 Feet
N65°W - Fence Post - 93.50 Feet
S72°W - Fence Post - 85.48 Feet
N78°E - Utility Pole - 129.00 Feet

Signed by D.B. Guthrie Date 9/19/95

Surveyor's Michigan License No. 22435

D-0374