

1995 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>44N</u>	R	<u>10W</u>	<u>E-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995
AM _____ PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie a field surveyor on 6/14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1849: Established by Wm. Ives, G.L.O. Survey - Set post and referenced Y.Birch 16 - S45W - 04 / Fir 12 - N67E - 17
- 1953: Survey by M.D.S.H. - Referenced corner
- 1989: Survey by Neil Hill - Found 1" Iron Pin in Monument Box.
- 1994: Road Design Survey by R.S. Scott Assoc. - Found Monument Box, re-set 1/2" Iron Rod by 1989 Neil Hill references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995: Found 1/2" Iron Rod in Monument Box 4.6 feet west of the centerline of Hwy. M-117.

SURVEY & REMONUMENTATION

DEC 01 1995

COUNTY

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 9-18-95

James H. Granger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Placed a 3" Aluminum Cap stamped to identify the corner on a 1/2"x24" Iron Rod located in a Monument Box.
 - Referenced - (Exist.) S35°E - 13" Apple - 173.42 Feet
 - (Exist.) N60°W - Utility Pole - 75.42 Feet
 - (Exist.) S60°E - 14" Apple - 122.08 Feet
 - (Exist.) N85°E - Chiseled "X" on the top of a steel Post - 189.08 Feet

Signed by D.B. Guthrie

Date 9/19/95

Surveyor's Michigan License No. 22435

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

D - 0375