

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |                                       |           |
|------------------------------------|---------------------------------------|-----------|
| 1. Public Land Survey              | T <u>44N</u> R <u>10W</u>             | <u>C6</u> |
|                                    | T _____ R _____                       | _____     |
|                                    | T _____ R _____                       | _____     |
|                                    | T _____ R _____                       | _____     |
| 2. Property Controlling in Section | S <u>18</u> T <u>44N</u> R <u>10W</u> | <u>7</u>  |
|                                    | S _____ T _____ R _____               | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____               | _____     |
|                                    | S _____ T _____ R _____               | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 19 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (C6) Quarter corner common to Sections 17-18. 1849: Established by M. Ives: North between 17 & 18...40.00 Set qr. section post. Y. Birch 7 S52W 18, Y. Birch 16 S75E 15...80.00 Set post corner of Sections 7,8,17, and 18.  
 (7-Sec. 18) North 1/16 corner between Sections 17 and 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (C6) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2637.73' north and south, being proportionate to the original record. Found an old squared cedar post about 7' west of the reestablished position, for an approximate corner. Placed the post adjacent to the monument.  
 (7-Sec. 18) Established the corner midway and on a line of mean true bearing between Section corner 1318.86' north and Quarter corner 1318.86' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (C6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 10" Maple S88W 24.65' "1/4S NBT"  
 8" Maple in clump S18E 24.0' do  
 18" W. Birch S84E 10.35' do  
 8" Maple N18W 20.35' do  
 Bearings are magnetic. Distances are to nail with tag.  
 (7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 8" Maple S83E 26.85' "N1/16 BT"  
 12" Maple N27E 24.0' do  
 10" Maple N39W 25.95' do  
 10" W. Birch S52W 12.0' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/14/02