

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Mackinac Co. Four Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. R. <u>11</u> <input checked="" type="checkbox"/> W.	F-6 8, Sec. 16 5, Sec. 16 12, Sec. 16
2. PROPERTY CONTROLLING IN SECTION	<u>16</u> , T. <u>44</u> N. R. <u>11</u> <input checked="" type="checkbox"/> W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. / S. R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 3/21 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-6 Placed Center Corner, Section 16, at intersection of lines connecting opposite  $\frac{1}{4}$  Corners.

8, Sec. 16 Placed West  $\frac{1}{16}$  Corner on line and midway bet. the West  $\frac{1}{4}$  Corner and the Center  $\frac{1}{4}$  Corner.

5, Sec. 16 Placed North  $\frac{1}{16}$  Corner on line and midway bet. the North  $\frac{1}{4}$  Corner and Center  $\frac{1}{4}$  Corner.

12, Sec. 16 Placed South  $\frac{1}{16}$  Corner on line and midway bet. the South  $\frac{1}{4}$  Corner and the Center  $\frac{1}{4}$  Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at F-6, 8, Sec. 16, and 5, Sec. 16.

F-6 Bearings: 14" Soft Maple S55 $\frac{1}{2}$ °W 36.1' and 16" Hemlock N14°E 5.4'

8, Sec. 16 Bearings: 8" Soft Maple S82°E 6.4' and 10" Soft Maple S26°W 9.6'

5, Sec. 16 Bearings: 8" Soft Maple S49°E 36.3' and 8" Soft Maple S34°W 39.5'

12, Sec. 16 Buried 1" x 36" pipe in South edge, County Road.  
 Bearings: 10" Soft Maple N50°W 67.6' and 14" Soft Maple N51°E 66.9'

SIGNED BY Billy D. Buckler DATE 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)