

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Mackinac Co. Two Corners

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. S., R. _____ E. W.	3, Sec. 16 10, Sec. 16
2. PROPERTY CONTROLLING IN SECTION	16 T. 44 N. S., R. 11 E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 8/25 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 3, Sec. 16 North 1/16 Corner, on West side, Sec. 16, placed midway between the NE Sec. Cor. and the West 1/4 Corner.
 - 10, Sec. 16 South 1/16 Corner, on West side, Sec. 16, placed midway and on line bet. the West 1/4 Corner and the SW corner, Sec. 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3, Sec. 16 Placed 1" pipe with 4" aluminium cap at corner.
Bearings:
8" Cedar S10°E 12.7'
12" Cedar S74°E 21.2'
- 10, Sec. 16 Buried 1" x 36" pipe in N-S County road, 17' South of County road to East.
Bearings:
10" Soft Maple N45°W 76.5'
12" Soft Maple S67°W 50.3'

SIGNED BY Billy D. Buckler DATE 9/13/72
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)