

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Machine Co. Two Corners

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. S. R. <u>11</u> E. W.	<u>F-5</u> <u>E-7</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 8/30 19 72, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- F-5 Original  $\frac{1}{4}$  Cor. bet. Secs. 9-16, set by William Ives, D.S. 1849.  
 bearings were:  
 Cedar 12" N65°W 06 Links  
 Cedar 8" S75°E 05 Links
  - E-7 Original Sec. Cor. 16-17-20-21, set by William Ives, D.S. 1849.  
 bearings were:  
 Beech 6" S69°E 24 Links  
 Beech 12" N44°W 50 Links
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- F-5 Found no evidence of corner or accessories, therefore re-established  $\frac{1}{4}$  corner midway and on line bet. two Sec. Cors.
  - E-7 Found no evidence of corner or witnesses; placed corner in intersection of roads to North, South, and West.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- F-5 Placed 1" pipe with 4" aluminium cap at corner.  
 New bearings:  
 10" W. Birch S6°W 20.3'  
 9" B. Cherry S55°W 44.0'
  - E-7 Buried 1" x 16" Iron Pin in road intersection.  
 New bearings:  
 8" Soft Maple S77°E 69.0'  
 10" Hemlock N72°E 64.3'

SIGNED BY: Billy D. Buckler DATE 9/13/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 6067 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_