

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Mackinac Co. Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. R. <u>11</u> E. W.	G-5 E-5
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- G-5 Sec. Cor. 9-10-15-16, set originally by William Ives, D.S. 1849.
 Bearings were:
 Y. Birch 7" S50°W 27 Links and Cedar 7" N60°E 31 Links
 - E-5 Sec. Cor. 8-9-16-17, set originally by William Ives, D.S. 1849.
 Bearings were:
 Cedar 8" N21°W 12 Links and Cedar 7" S12°E 34 Links

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-5 Found squared Cedar Post with several names, which were not discernible, with date 3/15/46. No evidence of original witnesses but position appears to agree with other corners in area.
 - E-5 Found a squared Cedar, at intersection of very old blazed lines from South, East and West. No evidence of original corner or witnesses; Corner lies on East edge of an old logging trail.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Placed 1" pipe with 4" aluminium cap at both corners.
 - G-5 New Bearings:
 - 18" W. Pine S52°W 70.5'
 - 7" S. Maple S3°W 25.6'
 - 8" Hemlock N54°W 35.8'
 - E-5 New Bearings:
 - 8" Cedar S80°E 14.3'
 - 7" Cedar S16°E 14.4'

SIGNED BY *Billy D. Buckler* Billy D. Buckler DATE 8/16/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)