

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. R. <u>11</u> W.	I-5 H-5
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/24 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-5 Sec. Cor. 10-11-14-15, set by William Ives, D.S. 1849.
Bearings were:
Beech 6" S38°W 49 Links and Sugar 8" N18°E 46 Links
- H-5 ¼ Cor. bet. Secs. 10-15 set by William Ives, D.S. 1849.
Bearings were:
Beech 6" N50°W 23 links and Beech 5" S23°E 24 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-5 Placed Corner in Center of E-W road, in line with fence to South and bet. two fences (50' apart). Distance checks well to Corners West.
- H-5 Placed Corner 25.0' East of an old fence corner and in line with roads to East and South. This falls exactly midway between the Sec. Cors.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-5 Buried 3/4" x 24" Iron in E-W road.
New Bearings: 24" Hard Maple N12°E 79.0'
13" Hard Maple N55°W 66.6'
- H-5 Placed 1" pipe with 4" aluminium cap at corner.
New Bearings: 14" Hard Maple S46°W 18.2'
28" Hard Maple N63°E 49.5'

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 8/16/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____