

Mackinac Co.

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970  
Mackinac Co. 3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	6-Sec.1
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>44</u> N. _____ S., R. <u>11</u> E. _____ W. _____	7-Sec.1
		9-Sec.1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-20, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 6-Sec.1 Northeast 1/16 Corner of Section 1.
- 7-Sec.1 North 1/16 Corner, on East side of Section 1.
- 9-Sec.1 East 1/16 Corner of Section 1.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 6-Sec.1 Placed corner at center of NE  $\frac{1}{4}$  Section.
- 7-Sec.1 Placed corner on line with Sec. Cors and 20.3' West of 2" Iron Pipe in Fence Line.
- 9-Sec.1 Placed corner midway bet. East  $\frac{1}{4}$  Corner and Center Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners.
- 6-Sec.1 Bearings: 24" W. Pine, N23°W, 25.0', 10" Beech, S73°W, 13.0' and 10" Beech, N37°E, 17.3'. Monument is buried in South rut of road.
  - 7-Sec.1 Bearings: 8" S. Maple, S52°W, 28.6' and 10" S. Maple, West, 28.2' and 2" Iron Pipe, East, 20.3'.
  - 9-Sec.1 Bearings: 14" Maple, North, 36.5' and 10" Maple, N50°E, 27.1' and 12" Beech, S38°W, 14.0'.

SIGNED BY Billy D. Buckler DATE 8-10-79  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_