

Mackinac Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. _____ E. _____ S., R. _____ W.		13-Sec.1
2. PROPERTY CONTROLLING IN SECTION 1 _____ T. 44 N. 11 E. _____ S., R. _____ W.		14-Sec.1
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W.		16-Sec.1
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-9, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 13-Sec.1 Southeast 1/16 Corner of Section 1.
- 14-Sec.1 South 1/16 Corner on East side of Section 1.
- 16-Sec.1 East 1/16 Corner on South side of Section 1.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 13-Sec.1 Placed Corner at center of SE 1/4 Section.
- 14-Sec.1 Placed Corner midway bet. Sec. Cor. to South and 1/4 Cor. to North.
- 16-Sec.1 Placed corner midway bet. Sec. Cor. to East, and 1/4 Cor. to West.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corners:

Placed 1" Pipe with 4" Aluminium cap at all corners.

- 13-Sec.1 Bearings: 8" Maple, S50°E, 3.7' and 10" Y. Birch, S31°W, 25.5' and 10" Twin Maples, S79°W, 22.1'
- 14-Sec.1 Bearings: 7" Aspen, S60°W, 27.2' and Twin 14" Cherry, S6°E, 66.8'.
Corner lies on East side of N-S road.
- 16-Sec.1 Bearings: 24" R. Maple, N74°W, 29.5' and 8" H. Maple, N25°E, 23.0'.

SIGNED BY Billy D. Buckler DATE 9-10-79
 BILLY D. BUCKLER

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____