

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

4 Corners.

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|---------------------------|
| 1. PUBLIC LAND SURVEY_____ | T. <u>44</u> ^{N.} S. , R. <u>11</u> ^{K.} W. | L-5, K-5 |
| 2. PROPERTY CONTROLLING IN SECTION <u>12</u> | , T. <u>44</u> ^{N.} S. , R. <u>11</u> ^{K.} W. | 16, Sec. 12 & 15, Sec. 12 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ ^{N.} S. , R. _____ ^{E.} W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-13, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Sec. Cor. and 1/4 Cor. set by Wm. Ives, D.S. in 1849. Bearings were:

L-5 1/4 corner bet. Sec's. 12-13. Beech 5", S50°W, 15 lks. & Beech 5", N34°E, 35 lks.

K-5 Sec. Cor. 11-12-13-14. Beech 6", S37°W, 40 lks. & Beech 8", N53°E, 33 lks.

16-Sec.12 East 1/16 corner on South side of Section 12.

15-Sec.12 West 1/16 corner on South side of Section 12.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-5 Placed corner midway and on line bet. two section corners.

K-5 Placed corner in center of East-West road and in line with a fence to South. Found remains of an old fence to North.

16-Sec.12 Placed corner midway bet. Sec. Cor. to East and quarter corner to West.

15-Sec.12 Placed corner midway and on line bet. sec. cor. to West and quarter corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Buried 36" "T" Iron in center of East-West road at all four corners. Bearings are:

L-5 10" H. Maple, S23°W, 57.0' & 14" H. Maple, N72°E, 69.8' & 16" H. Maple, N9°E, 54.5'.

K-5 6" H. Maple, N50°W, 43.6' & 12" H. Maple, N10°E, 27.7' & 8" H. Maple, N32°E, 37.3'.

16-Sec.12 26" H. Maple, N55°W, 50.3' & 12" Beech, N4°W, 63.4' & 12" Soft Maple, N50°E, 46.8'.

15-Sec.12 8" h. Maple, N42°W, 37.3' & 12" H. Maple, N51°E, 67.2'.


SIGNED BY Billy D. Buckler DATE 9-3-80
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____