

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. S. R. <u>11</u> E. W.	D-5
2. PROPERTY CONTROLL- ING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-1, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

-5 North 1/4 cor of sec. 17. Wood Post, Cedar 8", S40°E, 50 lks. & Tam. 5", N60°W, 87 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

-5 Found SE O.E.T, (Cedar 8", S40°E, 50 lks.) now 10" and down but still living with many branches now growing as trees. Both upper and lower faces plain with some axe marks but scriting weathered off. A tam. stp. with signs of scarring and overgrowth is at the proper bearing (N60°W) but the distance is somewhat short. It would be close if the numbers were inverted: I.E. 78 lks. instead of 87 lks. as recorded.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-5 D.N.R. Monument. New Bearings:

6" Cedar, N54°W, 56.2'
4" Cedar, South, 15.55'
5" Cedar, S40°E, 14.5'
4" Tam., N71°E, 33.4'

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: