

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
2. PROPERTY CONTROLL- ING IN SECTION <u>17</u> , T. <u>44</u> N. _____ E. _____ S., R. <u>11</u> W. _____		11, 12, 13
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-7, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 11 Southwest 1/16 Cor. Sec. 17. Not prev. est. (CENTER OF SW 1/4)
- 12 South 1/16 Cor. ^{N-S 1/4 corner} Sec. 17. Not prev. est.
- 13 Southeast 1/16 Cor. Sec. 17. Not prev. est. (CENTER OF SE 1/4)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 11 Set at center of Southwest 1/4 by closed traverse.
- 12 Set M.P.O.L. between center corner and South 1/4 corner.
- 13 Set at center of Southeast 1/4 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR. Monuments set at all three corners. Bearings:

11 6" Ealsam, S13°E, 6.35'	12 8" Twin R. Maple, S63°E, 11.9'	13 10" Ironwood, S77°E, 25.8'
6" Cherry, S80°W, 11.6'	5" R. Maple, N48°W, 28.1'	9" H. Maple, N59°W, 18.4'
6" Ealsam, N36°W, 12.85'	6" R. Maple, N19°W, 32.9'	6" H. Maple, S15°W, 42.3'
6" R. Maple, N28°E, 19.85'	6" R. Maple, N25°E, 23.2'	16" H. Maple, N23°E, 57.8'

Cor. sets in E-W fence line.

SIGNED BY David E. Babbitt
David E. Babbitt

DATE 1-27-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____

DATE _____