

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

3 Corners.

| FOR CORNERS OF--:   | LOCATED IN--:             | CORNER CODE NUMBER |
|---|---------------------------|--------------------|
| 1. PUBLIC LAND SURVEY_____ T. _____                         | N. S., R. _____ E. W.     | _____              |
| 2. PROPERTY CONTROLLING IN SECTION <u>11</u> , T. <u>44</u> | N. S., R. <u>11</u> E. W. | <u>2, 3, 5</u>     |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____       | N. S., R. _____ E. W.     | _____              |
| 4. LOT NO. _____ , RECORDED PLAT _____                      |                           |                    |
| 5. PRIVATE CLAIMS _____                                     |                           |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-12 & 9-20, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2 East 1/16 Corner on North side of Section 11. Not prev. set.
- 3 Northwest 1/16 Corner of Section 11. Not prev. set.
- 5 Northeast 1/16 Corner of Section 11. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Corner set M.P.O.L. between North 1/4 Corner and N.E. Section Corner of Section 11.
- 3 Corner set at center of N.W. 1/4 of Section 11 by closed traverse.
- 5 Corner set at center of N.E. 1/4 of Section 11 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
D.N.R. Monuments set at all three corners. Bearings:

- 2 8" H. Maple, S38<sup>0</sup>E, 27.3' & 10" H. Maple, N77<sup>0</sup>W, 5.7' & 6" H. Maple, N45<sup>0</sup>E, 16.3' & 8" Ironwood, S88<sup>0</sup>E, 13.6'.
- 3 8" B. Cherry, S60<sup>0</sup>E, 17.2' & 10" B. Cherry, S67<sup>0</sup>W, 12.5' & 10" Beech, N67<sup>0</sup>W, 23.0' & 8" H. Maple, East, 19.3'.
- 5 10" B. Cherry, N60<sup>0</sup>E, 19.2' & 10" Ironwood, S81<sup>0</sup>E, 20.7' & 7" H. Maple, S12<sup>0</sup>E, 13.5' & 7" H. Maple, N82<sup>0</sup>W, 33.1'.

SIGNED BY

Gerald L. Wiggins  
Gerald L. Wiggins

DATE 3-5-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

