

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION _____ 11 _____	N. _____ 44 _____ R. _____ S., R. _____ W. _____	10, 1
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-4 & 9-19, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 10 South 1/16 Corner on West side of Section 11. Not prev. set.
- 1 West 1/16 Corner on North side of Section 11. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 10 Corner set M.P.O.L. between West 1/4 Corner and S.W. Section Corner of Section 11.
- 1 Corner set M.P.O.L. between North 1/4 Corner and N.W. Section Corner of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D.N.R. Monument set at both corners. Bearings:


- | | | | |
|----|-----------------------------|---|-----------------------------|
| 10 | 12" R. Maple, N37°E, 15.25' | 1 | 14" H. Maple, S15°E, 40.80' |
| | 14" H. Maple, N85°E, 32.60' | | 14" R. Maple, S25°W, 37.25' |
| | 14" H. Maple, S52°E, 34.60' | | 12" H. Maple, S81°W, 31.50' |
| | 6" R. Maple, N78°W, 37.50' | | 8" R. Pine, N11°W, 29.80' |
| | 2" Pipe, buried, N8°E, 6.1' | | |

SIGNED BY

Gerald L. Wiggins
Gerald L. Wiggins

DATE 3-5-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: